

West Bengal Transport Infrastructure Development Corporation Limited

(A Government of West Bengal Undertaking)
"Paribahan Bhawan-II", Transport Department
E.M. Bye Pass & Rashbehari Connector Intersection
CSTC Kasba Depot Compound
Kolkata- 700 107

Tel. No. 2442 9081 / 9082

Fax. No. 2442 9082

E-mail: wbtidc@gmail.com

NIQ NO: - 008/WBTIDCL/E/2025-26

DATE: - 17/10/2025

NOTICE INVITING QUOTATION

WBTIDC Ltd. invite Quotations from bonafide, resourceful and experienced firms for undertaking the work – "Improvement and Seating Arrangement Works in Room No. 16, within WBTIDCL Office Premises, Paribahan Bhaban-II, CSTC Kasba Depot, E.M. Bye-Pass & Rashbehari Connector Crossing, Kolkata – 700107".

The quotationers should submitted the following certificates with the quotation: -

1. Valid Trade License
2. Valid PAN Registration
3. Valid GST Registration

The time of completion is 14 (fourteen) days from the date of issuance of work order.

Schedule of item for the said work is enclosed. Rate to be quoted based on the specified schedule of items.

The Quotation paper shall be submitted in sealed cover within **30.10.2025** by **15.00** hrs. and the same shall be opened at 16.00 hrs. on that date at the Office of the Managing Director, WBTIDC Ltd., E.M. Bye-Pass & Rashbehari Connector Intersection, CSTC Kasba Depot Compound, Kolkata- 700107.

Enclo. As stated.


Joint Managing Director
WBTIDC Ltd.

Copy forwarded for kind information to the: -

1. Chief Engineer, WBTIDC Ltd.
2. Executive Engineer, WBTIDC Ltd.
3. Assistant Engineer, WBTIDC Ltd., (D. Roychoudhary)
4. Accounts Officer, WBTIDC Ltd.
5. Head Assistant, WBTIDC Ltd.
6. Assistant Engineer, WBTIDC Ltd., (S. Choudhury)
7. Notice Board, WBTIDC Ltd. Office


Joint Managing Director
WBTIDC Ltd.

**Name Of Work: Improvement and Seating Arrangement Works in Room No. 16, within WBIDCL Office Premises,
Paribahan Bhaban-II, CSTC Kasba Depot, E.M. Bye-Pass & Rashbehari Connector Crossing, Kolkata - 700107.**

Sl. No.	Description of Works	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	Supplying, fitting and fixing boiling water resistant ply conforming to IS: 303- 1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per design as per approval and direction of Engineer-in- Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] In Ground Floor [Using cement slurry for bedding @4.4 kg/Sq.m and for jointing @1.8 kg/Sq.m] 19mm	29.50	Sqm	1871.00	55194.50
2	Supplying, fitting and fixing boiling water resistant ply conforming to IS: 303- 1989 bonded with phenol formaldehyde synthetic resin of approved make and brand fitted and fixed as per design as per approval and direction of Engineer-in- Charge.[excluding the cost of supporting frame work and teak wood batten/Lipping] In Ground Floor [Using cement slurry for bedding @4.4 kg/Sq.m and for jointing @1.8 kg/Sq.m] 12mm	10.32	Sqm	1290.00	13312.80
4	Supplying fitting, fixing decorative lamination conforming to IS: 2046 : 1995 as per approved make, brand, finish and thickness with fitting, fixing the same on Particle/MDF / Ply Boards with recommended / approved adhesive with proper clipping the sides for better attachment as per direction of Engineer-incharge. The rate includes the cost of labour, adhesive and all incidental charges thereof. In ground floor Thickness of laminate 1.5mm	19.00	Sqm	802.00	15238.00
				Total=	83,745.30
				Say:	83,745.00

(Rupees Eighty three thousand seven hundred forty five only)

Note: GST and other charges as applicable would be paid or deducted over the total bill amount.

On getting all information after site inspection as per scope of the work, the rates would be quoted accordingly.

I/We do hereby agree to carry out the whole work mentioned in the memorandum @
..... the schedule of items & rates specified in this schedule of works.

Signature of the Quotationer
with Date & Seal

SCOPE OF WORK & RESPONSIBILITY OF THE QUOTATIONER:

The scope of work covered under this quotation shall include supplying, fitting, and fixing of Boiling Water Resistant (BWR) Ply and Decorative Lamination in the Ground Floor as per approved design, make, brand, and as directed by the Engineer-in-Charge. The work shall be executed in accordance with IS standards and specifications, ensuring proper finishing, durability, and strength. Interested agencies should inspect the site prior to quoting to understand the exact nature of requirements.

1. Supplying & Fixing of BWR Ply (19mm):

- Boiling Water-Resistant Ply conforming to IS: 303-1989, bonded with phenol formaldehyde synthetic resin, of approved make and brand.
- Ply shall be fitted and fixed as per design and as directed by the Engineer-in-Charge.

2. Supplying & Fixing of BWR Ply (19mm):

- Boiling Water-Resistant Ply conforming to IS: 303-1989, bonded with phenol formaldehyde synthetic resin, of approved make and brand.
- Ply shall be fitted and fixed as per design and as directed by the Engineer-in-Charge.

3. Supplying & Fixing of Decorative Lamination (1.5mm):

- Decorative Lamination conforming to IS: 2046-1995, of approved make, brand, finish, and thickness.
- To be fixed on Particle/MDF/Ply boards using approved adhesive and properly clipped at the sides for better attachment.

Signature of the Quotationer
with Date & Seal